

Guadalupe Bayou Flow and Inundation Study

Final report to the BBASC

Richard Carothers, M.S.
Dr. Ben R. Hodges
Dr. Paola Passalacqua

Center for Research in Water Resources
University of Texas at Austin

September 30, 2015



Work accomplished


- Digital elevation model based on lidar data and detailed analyses.
- Inundation analysis using GIS tools.
- Field data collection for water levels, temperatures, and salinity.
- First stage of hydrodynamic modeling for connectivity in bayou.




Inundation Maps

Can be used to determine areas below any selected water height 1 and 2 ft above sea level shown.

Requires further analyses to evaluate connectivity between areas or to quantify areas at different water levels.



Digital Elevation Model




Sensor names

Field Sensors Deployed


Deployments
March 18-20, 2015
May 20-22, 2015

Data recovery May 20-22, 2015 Aug 19-20, 2015

Instrument recovery Aug 19-20, 2015











Raw data – Conductivity





Raw data – Temperature





Hydrodynamic model results

Tracers to illustrate connectivity.

Initial tracers shown at right.

Flow rates tested:

140 cfs

280 cfs

560 cfs


1120 cfs

1680 cfs

2800 cfs





10













0.8















14















Limits of hydrodynamic model

Hydraulic representation of gates is not presently included – requires more data on sizes of openings and their installation.

Channels narrower than 15 m are widened, which affects the modeled flow rates.

Full calibration/validation not done (not part of contract).

Model does not include areas outside of lidar data, which includes substantial catchment flows.

Model is useful for *qualitatively* understanding connectivity – not for *quantitatively* predicting response.



Recommendations for future work

- Analyses of field data.
- Development of inundation maps at water surface elevations of interest to the BBASC.
- Addition of gate flow behavior to the hydrodynamic model.



Concluding points

- Major thrusts of projects accomplished.
- Field data not as extensive as originally planned due to logistics and weather (some funds returned to state).
- Hydrodynamic model is workable, but is close to the limits that can be accomplished without going to a supercomputer.



Acknowledgements

Funding provide by BBASC recommendations to TWDB.

We would like to thank numerous personnel within TWDB, GBRA.

Particular help with setting of the field work has been provided by:

Kevin Kriegel, TPWD

Dan Alonso, SABAY



salDiv = at diversion canal salN = above diversion canal salBar = at barrier salS = below barrier nHogS = upper Hog Bayou 35div = diversion canal at hwy 35 mGuadN = N on main stem mGuadS = S on main stem IGuadN = lower Guadalupe schN = N sensor on Schwings Bayou schS = S sensor on Schwings Bayou mamS = Mamie Bayou entrance hogS = Hog Bayou entrance goffS = Goff Bayou entrance tc = planned, but not emplaced

